

NATIONAL PRECAST CONCRETE ASSOCIATION



Manual for Jointed Precast Concrete Pavement

3rd Edition



NPCCA

National Precast Concrete Association

Authors

Peter Smith, P.E.

Mark B. Snyder, Ph.D., P.E.

Graphic Designer

Deborah Templeton

NPCA Precast Concrete Paving Slabs Product Committee members (2018-2019):

Thomas Montalbine, Roman Stone Construction Co., chairman

Jim Aylward, Western Forms Inc.

Daryl Burns, Delta Specialty Precast Concrete Engineers

Dean Frank, P.E., Industry Consultant

Dan Moellman, P.E., The Fort Miller Co. Inc.

Alan Pritchard, Smith-Midland Corp.

Warren Taylor, Pro-Cast Products Inc.

Sam Tyson, Federal Highway Administration

Table of Contents

Chapter 1: Introduction

Pavement Repair: A Worldwide Necessity	1-2
What Is a Precast Concrete Pavement System?	1-2
Similarities to Cast-In-Place Systems	1-3
Precast Concrete Pavement Systems	1-4
General Categories of Precast Pavement Systems	1-5
Precast Prestressed Concrete Pavement (PPCP)	1-5
Jointed Precast Concrete Pavement (JPrCP)	1-6
Experience and Performance Expectations	1-7
Fabrication and Installation Experience to Date.....	1-7
Performance Indicators.....	1-8
Topics Covered in This Manual	1-10
Summary	1-10

Chapter 2: Criteria and Considerations for Using Precast Pavement Systems

Principal Criteria for Using Precast Pavement	2-1
Short Work Windows and/or Heavy Traffic	2-1
Long-Term Durability Required	2-2
Project Suitability: Other Factors for Consideration	2-2
General Constructability Considerations.....	2-2
Site-Specific Factors That May Impact Design and Construction.....	2-6
Summary	2-12

Chapter 3: Applications for Jointed Precast Pavement Systems

Types of Repair.....	3-1
Intermittent Repairs	3-1
Continuous Lane Replacement	3-3
Intermittent and Continuous Replacement in Adjacent Lanes.....	3-4
Precast Repair for Other Locations	3-5
Ramps	3-5
Urban Arterials	3-6
Intersections	3-6
City Streets.....	3-8
Toll Plazas.....	3-9
Bridge Approaches and Bridge Approach Slabs.....	3-9
Bus Pads	3-10
Pavement Under Low-Clearance Bridges.....	3-11
Precast Repairs for Composite Pavement	3-12
Repairs to Airport Pavement	3-13
Summary	3-14

Chapter 4: Design of Jointed Precast Concrete Pavement Systems

Structural Design Criteria	4-1
Service Life and Performance Criteria	4-2
Strength and Reinforcing Considerations	4-2
Typical Thickness Design Criteria.....	4-3
Typical Thickness Design Constraints.....	4-4
Panel Size Selection and Joint Layout Considerations	4-4
Panel Dimensions: Limiting Maximum Size and Aspect Ratio.....	4-5
Matching Transverse Joint Locations in Adjacent Lanes	4-5
Considerations for Retaining the Existing Longitudinal Joint Layout	4-6
Impact of Utility Access on Joint Layout	4-7
Consideration of Existing Expansion Joints.....	4-7
Selection of Slab Support System and Impact on System Design	4-9
Grade-Supported JPrCP Systems	4-9
Grout- and Urethane-Supported JPrCP Systems	4-11
Thickness Design	4-12
Considerations and Design Procedures for Lane Replacements and Reconstruction.....	4-12

JPrCP Panel Reinforcing	4-14
The Need for Panel Reinforcing	4-14
Slab Reinforcing Techniques	4-14
Design of Slab Reinforcing.....	4-15
Load Transfer Systems.....	4-17
Importance of Joint Load Transfer.....	4-17
Dowels, Tie Bars and Keyways – Uses and Limitations.....	4-18
Dowel Load Transfer System Design	4-20
Dowel and Tie Slot Systems – Design, Fabrication and Construction Considerations.....	4-25
Approval of New Load Transfer Systems	4-25
Tie Steel System Design	4-31
Additional Slab Design Features and Considerations.....	4-33
Embedded Features: Lifting and Jacking Hardware	4-33
Embedded Features: Utility Openings.....	4-35
Slab Surface Texture, Color, Patterns.....	4-35
Grout Distribution Systems (Grout Ports and Distribution Channels).....	4-35
Summary	4-36

Chapter 5: Developing Plans, Specifications and Cost Estimates

Specifications	5-1
Historical Perspective	5-1
Types of Specifications in Current Use	5-2
Essentials for Specifications of All Types.....	5-6
Preparing Contract Plans.....	5-6
Typical Sections	5-6
Maintenance and Protection of Traffic.....	5-6
Precast Panel Details	5-7
Installation Details	5-7
Repair Locations	5-8
Developing Project Costs.....	5-8
What to Include in Project Costs	5-8
Sources of Installed Cost Information.....	5-8
Factors That Affect Project Cost.....	5-9
Estimating Project Time Requirements	5-11
Project Award.....	5-11
Contractor Mobilization and Subcontractor Awards	5-11
Surveying.....	5-11
Development and Approval of Shop Drawings	5-12
Fabrication	5-12
Time for Installation	5-12
Time for Joint Sealing, Profile Grinding and Cleanup	5-12
Comparing PCP Costs with Other Paving and Repair Technique Costs	5-13
Summary	5-14

Chapter 6: Shop Drawings and Other Submittals

Starting The Shop Drawing Process – Gathering Necessary Information	6-1
Information Gathered From Contract Plans and Specifications.....	6-1
Information Gathered From Contractors	6-4
Information Gathered From System Designers.....	6-6
Information Gathered From Precasters.....	6-6
Pre-Construction Meeting.....	6-6
Shop Drawing Content	6-6
Production Note Sheet	6-7
Panel Detail Sheets	6-7
Site Drawing Indicating Panel Layout	6-15
Shop Tickets.....	6-15
Summary	6-17

Chapter 7: Fabrication of Precast Pavement Panels

Precast Plant Facilities and Resources	7-1
Physical Facilities	7-1
Human Resources	7-2
Plant Certification Programs	7-2
Elements of a Plant Certification Program	7-2
Plant- and Product-Specific Quality Control Plans.....	7-3
Quality Control Personnel	7-3
Senior Management	7-3
Quality Control Manager	7-4
Quality Control Inspectors.....	7-4
Production Personnel.....	7-4
Special Requirements for Materials Used In Precast Panels	7-4
Aggregates	7-4
Cement	7-5
Supplementary Cementitious Materials (SCMs)	7-5
Chemical Admixtures	7-5
Concrete Mix Designs for Precast Panels	7-5
Forms for Precast Pavement Panels	7-6
Form Types.....	7-6
Beds for Flat (Single-plane) Panels.....	7-6
Beds for Non-planar Panels	7-7
Standard Side Rails	7-8
Side Rails for Variable-Width and -Length Panels.....	7-9
Preparation for Concrete Placement	7-10
Form Setup	7-10
Placement of Reinforcement.....	7-11
Pre-pour Checking.....	7-13
Concrete Placement, Finishing and Initial Curing.....	7-14
Concrete Testing	7-14
Concrete Placement	7-14
Screeding	7-14
Finishing and Texturing.....	7-14
Initial Curing	7-15
Post-placement Activities.....	7-16
Stripping Forms.....	7-16
Post-pour Checking.....	7-16
Panel Detailing	7-16
Panel Labeling.....	7-16
Final Curing	7-18
Yard Storage and Handling.....	7-18
Shipping	7-19
Summary	7-19

Chapter 8: Pre-Installation Procedures Common to All Systems

Maintenance and Protection of Traffic (MPT) and Providing Worker Safety.....	8-1
Work Areas	8-2
Pre-installation Field Surveying (Layout)	8-3
Laying Out Panel Point Marks for Area Placements	8-10
Laying Out Panel Point Elevation Marks in Area Placements	8-10
Sawing Operations	8-11
Removal of Existing Pavement.....	8-12
Subbase Repair	8-15
Working with Existing Cement-Treated Base	8-16
Replacement of Existing CTB with New, Rapid-Setting Lean Concrete Base.....	8-17
Drainable Concrete and Asphalt Bases	8-17
Summary	8-17

Chapter 9: System-Specific Installation Procedures

Placing or Adjusting Panels to the Correct Grades.....	9-1
Determining Correct Grades.....	9-1
Grades for Drop-in and Lane-replacement Panels	9-1
Grade Control for Grade-supported Systems	9-2
Grade Control for Grout-supported Systems.....	9-4
Grade Control Using Expansive Polyurethane Foam.....	9-4
Providing Complete and Uniform Panel Support.....	9-6
Grade-supported Systems.....	9-6
Grout-supported (Leveling-Lift) Systems	9-9
Urethane-supported Systems	9-10
Installing Load Transfer Devices at Transverse Joints.....	9-10
Top-Slot Methods.....	9-11
Bottom-Slot Method (The Fort Miller Super-Slab System).....	9-12
Sliding Dowel Methods.....	9-14
California Cast-Slide (Tear-Drop) Narrow Top-Slot System	9-16
Epoxy-Anchoring Dowels in Existing Pavement – All Methods	9-18
Tie Bars Across Longitudinal Joints.....	9-19
Generic Tie Bar Installation Procedures.....	9-19
Panel Placement.....	9-21
Preparing the Subgrade Surface.....	9-21
Equipment for Placing Panels	9-21
Panel Placement Under Overpasses	9-23
Positioning Panels Horizontally	9-23
Opening Panels to Traffic	9-24
Grade-supported Panels.....	9-24
Grout-supported Panels	9-25
Urethane-supported Panels	9-25
Achieving Smooth Pavement Surfaces	9-25
Selecting Methods That Work Together as a System.....	9-25
Benefits of Choosing an Established System.....	9-26
Considerations for Developing a New System	9-27
Summary	9-27

Chapter 10: Organizing and Managing a Project for a Quality Installation

Beginning a Precast Paving Project – System Validation.....	10-1
Validating Systems Before the Bid.....	10-1
Validating Systems After the Bid.....	10-2
System Trial Installation Meeting.....	10-2
System Trial Installation.....	10-2
Pre-construction Meeting	10-3
Fabrication Quality Control (QC) Plans and Quality Assurance (QA) Programs	10-4
Fabrication Quality Control (QC) Plans	10-4
Fabrication Quality Assurance (QA) Activities	10-4
Effectiveness of Fabrication QC Plans and QA Programs.....	10-4
Installation QC Plans and QA Programs.....	10-5
The Need for Installation (Contractor) QC and QA Programs	10-5
The Evolution of Installation QC Plans.....	10-5
Effective Contractor-generated Installation QC Plans.....	10-5
QC Plan Details – What to Check and Control.....	10-6
Owner's Installation QA Program	10-7
Installation Plan	10-8
Contractor Installation Crews	10-8
Project Manager.....	10-8
Surveying Crews.....	10-9
Shop Drawing Engineers	10-9
Sawing Crew.....	10-9
Removal Crew	10-10

Subbase Preparation Crew	10-10
Panel Placement Crew	10-11
Grouting Crew	10-12
Contractor QC Crew	10-12
Pre-installation Meeting	10-13
Training	10-13
Trainer Selection	10-14
Classroom Training Topics	10-14
Training Examination and Certification	10-15
Contractor Trial Installation (Test Strip)	10-15
Modifying Installation Procedures After the Contractor Trial Installation	10-15
Emergency Provisions	10-15
Working Together	10-16
Cost Of QC/QA Plans and Programs	10-16
Summary	10-16

Chapter 11: After Panel Installation – The Finishing Touches

Spall Repair	11-2
Identifying Minor Defects in Need of Repair	11-2
Spall Repair Procedures and Materials	11-2
Repair of Defective Dowel Installations	11-3
Cracks in Precast Pavement Panels	11-3
Finding Cracks	11-3
Measuring Crack Widths	11-4
Crack Evaluation	11-5
Remediating Typical Cracks	11-6
Remediating Wide Cracks	11-6
Remediation of Excessive Joint Widths	11-6
Remediating Transverse Joints	11-7
Remediating Longitudinal Joints	11-7
Removing and Replacing Unacceptable Panels	11-8
Removing UngROUTED Bottom-Slot Panels	11-8
Removing Grouted Panels	11-9
Diamond Grinding	11-10
Grinding to Improve Pavement Smoothness	11-10
Grinding to Meet Pavement Profile Requirements	11-12
Grinding to Meet Pavement Friction Requirements	11-13
Sealing (or Not Sealing) Precast Pavement Joints	11-13
Mechanics of Successful Joint Sealing	11-14
Joint Filler Material	11-15
Joint Sealant Materials	11-16
Sealing Transverse Joints	11-16
Sealing Longitudinal Joints	11-18
Summary	11-19

Chapter 12: Precast Concrete Pavement Maintenance Requirements

Typical PCP Features and Conditions Requiring Maintenance	12-2
Identifying and Quantifying Distresses	12-2
Typical Maintenance and Repair Operations	12-3
Replacing Construction-related Spall Repairs	12-3
Repairing Failed Load Transfer Dowels	12-3
Repairing Excessively Wide Grout-filled Joints	12-4
Maintaining Joint Sealant in Precast Pavement	12-5
Maintaining Grout in Grout Ports and Lift Insert Recesses	12-6
Crack Maintenance	12-7
Full-depth Panel Replacement	12-7
Surface Texture Maintenance	12-7
Maintenance of Adjacent Original Pavement	12-8
Summary	12-8

Chapter 13: Future Applications for Jointed Precast Concrete Pavement

Addable Precast Concrete Pavement	13-1
Dowel Bar Retrofit Method	13-2
Bottom Slot and Solid Dowel Method.....	13-2
Bottom Slot and Removable (Hollow) Dowel Method	13-3
Reusable Urban Pavement	13-4
Overlay and Inlay Precast Panels	13-5
Precast Overlays	13-5
Precast Inlays.....	13-5
Precast Inlays in Existing Asphalt Pavement.....	13-6
Pilot Precast Panel Inlay Project.....	13-6
Pervious Precast Concrete Pavement Panels	13-7
Pervious CIP Concrete.....	13-7
Pervious Precast Pavement	13-8
Precast Panels for Industrial Use	13-9
Commercial Driveways.....	13-9
Acid- and Abrasion-resistant Industrial Floor Panels	13-9
Instrumented Pavement.....	13-10
Battery-charging Roadway Panels.....	13-11
Precast Recharging Panels	13-12
Heated Precast Pavement	13-13
Solar Power-generating Pavement Panels	13-13
U.S.-based Efforts	13-13
European Efforts	13-14
The Role of Precast Panels	13-15
Summary	13-15